



The Rajkumar College

Since 1870

Rajkot - 360001 Gujarat (India)
Phone : 0281 - 2466064, 2481032
Website : www.rkcrajkot.com
email : office@rkcrajkot.in
principal@rkcrajkot.in

TENDER FOR RENOVATION OF RANJITSINGHJI SWIMMING BATH (ONLY LABOUR)

DATE: 25/05/2026

The Rajkumar College, Rajkot is inviting sealed tenders for renovation of Ranjitsinhji Swimming Bath (swimming pool deck, walls and washrooms).

❖ SCOPE OF WORK

Demolition and re-application of tiles in Ranjitsinhji Swimming Bath as per details given.

❖ TENDER SUBMISSION

Tender issue date: 25/05/2026

Last date & time for submission: 01/06/2026 by 12:00 PM IST.

Tender Fees: 1000/-

❖ TIMELINE FOR THE PROJECT

All application and masonry work should be completed by 10th July, 2026.

❖ PAYMENT & OTHER CONDITIONS

- All government taxes must be included in the pricing.
- 25% Payment after demolition, 25 after IPS and plaster work and 25% RCC WALL and RCC raft slab and 25% after successful, timely and satisfactory completion of work.

BURSAR

THE RAJKUMAR COLLEGE, RAJKOT

Contractor's details: _____

Address: _____

Contact details: _____

Tender submission date: _____

PAN/GST DETAILS: _____

AADHAR DETAILS: _____

(IN CASE OF PROPRIETORSHIP FIRM)

Signature of the contractor: _____





TENDER FOR FURNITURE WORK WITH LABOUR AND MATERIALS

SR. NO	DESCRIPTION	Area	Unit	RATE	ESTIMATED AMOUNT
1	DEMOLITION WORK Demolition of existing tiles on the deck (floor tiles), walls (wall tiles), both bathrooms and inside the swimming pool.	9900	SQ FT		
2	IPS WORK Providing and laying India Patent Stone (IPS) flooring with mix proportion of 1:1.5:3 on the entire flooring.	5100	SQ FT		
3	PLASTER WORK Providing and applying cement plaster on walls, columns in single coat with mix proportion of 1:5 or 1:6. This includes wall on the deck of swimming pool up to 4ft and all washrooms up to 10 ft height.	4800	SQ FT		
4	APPLICATION OF TILES (WASHROOMS) Applying of tiles on wall dedo and flooring of size 12X18/12X24/ with application in chemical provided.	3300	SQ FT		
5	APPLICATION OF TILES (DECK AREA) Applying of tiles on wall dedo and flooring of size 12X18/12 X24/12X12/8X8 with application in chemical provided.	3625	SQ FT		
6	APPLICATION OF TILES (DECK AREA) Applying of tiles on wall dedo and flooring of size 12X18/12 X24/12X12/8X8 with application in chemical provided.	2900	SQ FT		
7	RCC WALL 4" THICK (INNER AREA OF POOL) Application of cement concrete of grade M20 of including the cost of steel binding, centring and shuttering work using wooden ply.	1245	SQ FT		





The Rajkumar College

Since 1870

Rajkot - 360001 Gujarat (India)
Phone : 0281 - 2466064, 2481032
Website : www.rkcrajkot.com
email : office@rkcrajkot.in
: principal@rkcrajkot.in

	<i>Ready mix concrete to be provided by the institution.</i>				
8	RCC RAFT SLAB 6" THICK (INNER AREA OF POOL) Application of cement concrete of grade M20 including the cost of steel binding.	1600	SQ FT		
9	PCC WORK 3" THICK Application of cement concrete of grade M10.	1600	SQ FT		
				TOTAL AMOUNT	

TERMS & CONDITIONS

- I. The above measurement is approximate and final measurement taken on site as per school engineer to be considered.
- II. All debris to be removed from the swimming pool and placed at suitable location outside as directed by the engineer.
- III. Rate should include all type of labour charges i.e. stacking/unstacking of tiles and other goods, to and fro from the site.
- IV. Steel binding should be as per structural design.
- V. After completion of work, entire site should be cleaned and handed over to the school.
- VI. Final payment will only be made after satisfactory completion of work, cleaning and approval by the engineer.

