



TENDER FOR EXTENSION OF PREP LODGE (WITH LABOUR & MATERIALS)

The Rajkumar College, Rajkot is inviting tenders for dry wall partition in Prep Lodge as per design given.

SCOPE OF WORK

Providing of 4 rooms on the terrace of the Prep lodge located at the Rajkumar College, Rajkot.

TENDER SUBMISSION

Tender issue date: 24/06/2026

Last date & time for submission: 02/07/2026 by 12:00 PM IST.

Tender Fees: 1000/-

DELIVERY & INSTALLATION

The said work must be completed by 29th July, 2026 at The Rajkumar College, Rajkot.

PAYMENT & OTHER CONDITIONS

- All government taxes and transportation must be included in the pricing.
50% Payment advance and 50% after successful, timely and satisfactory delivery of goods.

Handwritten signature of the Bursar

BURSAR

THE RAJKUMAR COLLEGE, RAJKOT

Contractor's details:

\_\_\_\_\_

Address:

\_\_\_\_\_

\_\_\_\_\_

Contact details:

\_\_\_\_\_

Tender submission date:

\_\_\_\_\_

PAN/GST DETAILS:

\_\_\_\_\_

AADHAR DETAILS:

(IN CASE OF PROPRIETORSHIP FIRM)

\_\_\_\_\_

Signature of the contractor:





TENDER FOR CONSTRUCTION/ ASSEMBLE AND FABRICATION WORK WITH LABOUR AND MATERIALS

SR. NO	DESCRIPTION
	<p><b>DRY WALL PARTITION (Area 1900 SQ FT)</b></p> <ul style="list-style-type: none"> <li>➤ Providing and fixing dry wall partition of 75mm thickness and 12ft height HCG panels for classroom partition as per the design given.</li> <li>➤ Providing and fixing dry wall partition of gypsum board above the 12ft high HCB panels.</li> </ul> <p><b>FABRICATION/ROOFING WORK (Area 2250 SQ FT)</b></p> <ul style="list-style-type: none"> <li>➤ Providing and fixing GI roof of JSW colour on plus of size 45ft x 50ft with 12mm insulation as per the design.</li> <li>➤ 3"x3" Angles to be used for partition support.</li> <li>➤ Providing and fixing KHECHI/TRUSS for roof support should be made with 4"x2" MS Pipe with 2mm thickness.</li> <li>➤ Providing and fixing vertical support with 4"x4" MS pipe of 2mm thickness for the structure.</li> <li>➤ Providing and fixing Perlin support with 4"x2" MS pipe of 2mm thickness for the structure.</li> <li>➤ Providing and fixing aluminium C channel in floor of size 75mm width.</li> </ul> <p><b>DECK SLAB</b></p> <ul style="list-style-type: none"> <li>➤ Providing and fixing deck slab of Everest/HCG cement sheet of 18mm thickness as per the drawing.</li> <li>➤ Providing and fixing C channel for deck slab support 4"x2" MS channel.</li> </ul> <p><b>FALSE CEILING WORK</b></p> <ul style="list-style-type: none"> <li>➤ Providing and fixing false ceiling with EVEREST/HCG cement sheets of size 600 x 600 mm in all classrooms.</li> </ul>
	<b>TOTAL COST OF PROJECT:</b>





# The Rajkumar College

Since 1870

Rajkot - 360001 Gujarat (India)

Phone : 0281 - 2466064, 2481032

Website : www.rkcrjakot.com

email : office@rkcrjakot.in

: principal@rkcrjakot.in

FOR OFFICE USE ONLY

We agree to carry out this work as per rates quoted and design as per sample dorm shown and following conditions of tender and instructions from supervisory staff, Bursar and Principal of The Rajkumar College, Rajkot.

## CONTRACTOR

## INTERNAL REMARKS:



TENDER ALLOTTED/ NOT ALLOTTED

BURSAR,  
THE RAJKUMAR COLLEGE, RAJKOT

